



CITY OF ALBANY

SITE IMPROVEMENT PROJECT

PRIVATE ENGINEERING INSPECTION SUBMITTALS

STREET

- _____ Compaction test results – subgrade. Wheel roll tests may be allowed if approved by the City representative and witnessed by both the City representative and private engineer.
- _____ Grade check sheet - subgrade
- _____ Grade check sheet - base rock
- _____ Compaction test results - base rock
- _____ Concrete test results for curb and gutter
- _____ Asphaltic concrete pavement compaction test results
- _____ Concrete pavement test results

STORM DRAIN

- _____ Compaction test results - trench backfill
- _____ Mandrel pull test results (for flexible pipe)
- _____ Grade check sheets - manholes and pipework
- _____ Video inspection documentation

SANITARY SEWER

- _____ Compaction test - trench backfill
- _____ Mandrel pull test results (for flexible pipe)
- _____ Grade check sheets - manholes and pipework
- _____ Manhole leakage test results
- _____ Pipe leakage test calculations and results
- _____ Video inspection documentation

WATER

- _____ Compaction test results - trench backfill
- _____ Pressure and leak test calculations and results
- _____ Disinfection procedure plan
- _____ Disinfection test results
- _____ Bacterial test results from a state certified water lab

MATERIAL SUBMITTALS

- _____ Rock source, gradation analysis, and proctor
- _____ Asphaltic concrete job mix formula
- _____ Portland cement concrete mix designs

Submittals also required for materials not listed in the Standard Construction Specifications.